

ENGINEERING DEPARTMENT**BANGALORE DIVISION.***Notification dated 5th January 1928.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 16th January 1928, for restoring Vandarakuppe Seshainakere Register No. 98 of Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :--

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Vandarakuppe Seshainakere in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for Restoring Vandarakuppe Seshainakere Hosakere
Registered No. 98 of Chennapatna Taluk, Bangalore District

No.	Items of work	Quantity	Per
	Bund—		
1	Clearing jungle	Lump sum	
2	Earthwork to bund including watering and tamping, etc.	9587	C.yd.
3	Turfing	4845	S.yd.
4	Resetting old stone work	50	C.yd.
5	New stone work	950	"
6	Providing new grade stones including cutting figures and painting, etc.	18	Each
7	Providing Index stones	18	"
8	Do Register number stone	1	"
9	Do B. M. stones	2	"
10	Do Date stone	1	"
11	Do Gauge stone	1	"
	Constructing Clay Puddle Wall—		
12	Earthwork mixed with sand	92	C.yd.
13	Clay puddle	220	"
14	Lead for earth available from draft and approach clearing at Waste Weir.	1035	"
	Constructing a Masonry Sluice—		
15	Earthwork excavation	11	C.yd.
16	Burnt stone jolley concrete in surki mortar	95	C.ft.
17	Do slabs dressed and fixed	189	S.ft.
18	Plastering with surki mortar	2'88	S.qr
19	Cement pointing	0'63	"
20	Burnt stone slabs for orifices, etc.	3	Each
21	Plug and rod with locking arrangement	Lump sum	
22	Earthwork cutting bund and refilling the same with watering and tamping.	180	C.yd.
	Waste Weir—		
23	Earthwork draft and approach clearing	1035	C.yd.
24	Rough stone work new	28	"